



Fluid Facts

Only EFI

Engineered Fluid, Inc.

www.engineeredfluid.com

www.enclosuresforindustry.com

Factory-Built Well Head Treatment Stations Solve Problems of Design, Cost and Completion Time

Rapid design turnaround, lower installed cost and higher quality give high value to factory-built well head treatment stations. Chemical feed, water treatment and system controls are built in.



GENEVA, NEBRASKA

A pre-assembled, well water treatment station is being set over the well head and foundation for a simple, cost effective installation.

Fluid Facts



Assembled piping takes water from the well head into the adjacent chemical feed room, all inside a factory-built station delivered complete to the jobsite.



Well starter, feed rate controllers, residual analyzer, turbidimeter, sample sink and level sensor are built into a submersible well pump, water treatment plant.

FluidFacts



A well head Hypochlorite Feed System with bulk storage, day storage, transfer pumps, feed pumps and controls in a pre-assembled building.



A pH Adjustment System with mix tank, feed pumps, piping and control system is built into one room of a factory-built, well head treatment facility.



Visit us online at www.engineeredfluid.com or www.enclosuresforindustry.com